

7551 Court Street · P.O. Box 217 · Elizabethtown, New York 12932 Telephone (518) 873-3332 · Fax (518) 873-3339

Daniel L. Palmer
County Manager

Linda M. Wolf
Purchasing Agent

TO: All Bidders

FROM: Linda Wolf, CPA, Purchasing Agent

DATE: March 2, 2015

SUBJECT: Addendum #3 GULF BROOK RESTORATION PROJECT


This Addendum, issued to bid document holders of record, indicates changes to the bid documents for the RFP for *GULF BROOK RESTORATION PROJECT* Opening March 6, 2015.

Please see attached list of QUESTIONS & ANSWERS regarding this project.

END OF ADDENDUM #3

Keene Questions:

- Does Geotechnical borings for the replacement of the existing Bucks Lane Bridge designed by Schroder in 1997 exist? Do record drawings exist? Existing bridge shows up as a 27' span, 19' out to out with a 6.034 condition rating (75.5 federal) with an AADT of 20. Would the longer span structure proposed still be functionally classified as a single lane bridge as you meet the criteria for such. Boring information is not available. Attached are four prints from the design set – they are not as-builts. The most recent bridge inspection report is also included. A single lane bridge is sufficient for this crossing.
- 2. Is ROW part of the scope? What about property access/easements and any necessary acquisition for construction access. ROW for Bucks Road appears to be approx. 2 rod with property owners owning to center of stream. Property access permissions/easements will be necessary and acquisition will be the responsibility of the consultant.



GENERAL NOTES

- 1. TYPE OF CONTRACT: LUMP SUM
- DESIGN SPECIFICATIONS: AASHTO STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES 1992 WITH INTERIM SPECIFICATIONS BRIDGE 1993.
- 3. MATERIAL SPECIFICATIONS: NEW YORK STATE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS, CONSTRUCTION AND MATERIALS, DATED JANUARY 2, 1990.
- 4. BRIDGE DESIGN CRITERIA: THE REPLACEMENT BRIDGE SHALL BE A PRECAST REINFORCED PORTLAND CEMENT CONCRETE BRIDGE STRUCTURE, IN ACCORDANCE WITH SPECIFICATION SECTION Ø3412, WITH CAST—IN—PLACE CONCRETE FOOTINGS. THE FOLLOWING PARAMETERS SHALL BE UTILIZED IN THE DESIGN OF THE PRE—ENGINEERED BRIDGE.
 - -LIVE LOAD: HS2Ø-44 -MIN. OPEN AREA FOR STREAM FLOW AS INDICATED.
- 5. A SUBSURFACE INVESTIGATION WAS COMPLETED AT THE PROJECT SITE BY ATLANTIC TESTING LABORATORIES, LTD. ON JANUARY 2, 1997. COPIES OF THE SUBSURFACE INVESTIGATION REPORT ARE AVAILABLE FOR REVIEW FROM ESSEX COUNTY. EXISTING SOIL CONDITIONS NOTED IN THE REPORT MAY NOT BE REPRESENTATIVE OF ACTUAL FIELD CONDITIONS. THE CONTRACTOR MAY TAKE ADDITIONAL BORINGS PRIOR TO BID. NO ADDITIONAL PAYMENTS FOR DIFFERING SUBSURFACE CONDITIONS SHALL BE PERMITTED.
- 6. THE NEW RETAINING WALLS SHALL BE CONCRETE CRIB TYPE RETAINING WALLS IN ACCORDANCE WITH SPECIFICATION SECTION Ø3411.
- 7. STREAM PROTECTION: DURING THE COURSE OF CONSTRUCTION, THE CONTRACTOR SHALL CONDUCT HIS OPERATIONS IN SUCH A MANNER AS TO PREVENT OR REDUCE TO A MINIMUM ANY DAMAGE TO ANY STREAM FROM POLLUTION BY DEBRIS, SEDIMENT, OR OTHER FOREIGN MATERIAL, OR FROM MANIPULATION OF EQUIPMENT AND/OR MATERIALS IN OR NEAR SUCH STREAMS. HE SHALL NOT RETURN DIRECTLY TO A STREAM ANY WATER WHICH HAS BEEN USED FOR WASH PURPOSES OR OTHER SIMILAR OPERATIONS WHICH CAUSE THIS WATER TO BECOME POLLUTED WITH SAND, SILT, CEMENT, OIL, OR OTHER IMPURITIES. IF HE USES WATER FROM A STREAM, HE SHALL CONSTRUCT AN INTAKE OR TEMPORARY DAM REQUIRED TO PROTECT AND MAINTAIN WATER RIGHTS AND TO SUSTAIN FISH LIFE DOWNSTREAM.
- 8. THE CONTRACTOR'S ATTENTION IS DIRECTED TO THE FACT THAT, DUE TO THE NATURE OF RECONSTRUCTION PROJECTS, THE EXACT EXTENT OF RECONSTRUCTION WORK CANNOT ALWAYS BE ACCURATELY DETERMINED PRIOR TO COMMENCEMENT OF THE WORK. THESE CONTRACT DOCUMENTS HAVE BEEN PREPARED BASED ON FIELD INSPECTION, FIELD SURVEYS AND OTHER AVAILABLE INFORMATION. ACTUAL FIELD CONDITIONS MAY REQUIRE MODIFICATIONS TO CONSTRUCTION DETAILS AND WORK QUANTITIES. THE CONTRACTOR SHALL PERFORM THE WORK IN ACCORDANCE WITH ACTUAL FIELD CONDITIONS.
- 9. THE CONTRACTOR SHALL PERFORM ALL WORK WITH CARE SO THAT ANY MATERIALS WHICH ARE TO REMAIN IN PLACE, OR WHICH WILL REMAIN THE PROPERTY OF ESSEX COUNTY, WILL NOT BE DAMAGED. IF THE CONTRACTOR DAMAGES SUCH ITEMS, THE DAMAGED ITEMS SHALL BE REPAIRED OR REPLACED IN A MANNER SATISFACTORY TO THE ENGINEER AT THE EXPENSE OF THE CONTRACTOR.
- 1Ø. THE BRIDGE SHALL BE CLOSED TO TRAFFIC DURING ALL DEMOLITION AND CONSTRUCTION OPERATIONS.
- 11. CONTRACTOR SHALL PROVIDE TEMPORARY SHORING AND/OR UNDERPINNING FOR HOUSE STRUCTURE AT NORTHEAST CORNER OF BRIDGE DURING ALL DEMOLITION AND CONSTRUCTION OPERATIONS. PROVIDE METHOD OF PROPOSED TEMPORARY SHORING TO ESSEX CO. FOR REVIEW PRIOR TO PERFORMING ANY WORK IN THIS AREA.
- 12. ESSEX COUNTY HAS A MEMORANDUM OF UNDERSTANDING WITH THE NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION TO WORK ON BRIDGES CROSSING WATERWAYS. ANY ADDITIONAL PERMITS REQUIRED SHALL BE OBTAINED BY THE CONTRACTOR.
- 13. UNDERGROUND PIPE LINES AND UTILITY LOCATIONS, IF INDICATED, ARE BASED ON VISUAL EVIDENCE OF UTILITIES AND PIPE LINES ABOVE EXISTING GRADE AND ARE APPROXIMATE ONLY. THE CONTRACTOR SHALL DETERMINE LOCATIONS OF ALL UNDERGROUND UTILITIES AND PIPELINES BEFORE COMMENCING CONSTRUCTION AND SHALL PROTECT AND/OR REROUTE SUCH ITEMS AS ORDERED BY THE ENGINEER, UNLESS NOTED OTHERWISE.
- 14. CONTRACTOR SHALL DEVELOP PROPOSED METHODS FOR DEWATERING EXCAVATIONS AND FOR MAINTENANCE AND TEMPORARY DIVERSION OF STREAMFLOW WITH ESSEX COUNTY PERSONNEL. ALL CONSTRUCTION BELOW STREAM WATER ELEVATION AND/OR GROUNDWATER ELEVATION SHALL BE DEWATERED TO THE SATISFACTION OF THE ENGINEER. PLACEMENT OF CRUSHED STONE. BACKFILL OR CONCRETE BELOW WATER SHALL NOT BE PERMITTED.
- 15. CONTRACTOR SHALL PROVIDE ADEQUATE SHORING AND/OR SHALL SLOPE ALL EXCAVATIONS IN STRICT ACCORDANCE WITH ALL APPLICABLE OSHA, STATE AND LOCAL REGULATORY REQUIREMENTS.
- 16. THE FOLLOWING WORK SHALL BE PERFORMED BY ESSEX COUNTY AND/OR THE TOWN OF KEENE:
 - A. MATERIAL AND INSTALLATION FOR NEW GUARD RAIL AT ALL LOCATIONS.
 - B. MATERIAL FOR NEW BRIDGE RAIL.
 - C. MATERIAL AND INSTALLATION FOR ALL NEW PAVEMENT AND SUBBASE.

 D. TEMPORARY RELOCATION OF EXISTING WATER LINE AND VALVES DURING
 - D. TEMPORARY RELOCATION OF EXISTING WATER LINE AND VALVES DURING CONSTRUCTION.
- E. PROVIDING MATERIAL FOR BACKFILL AND CRUSHED STONE FOR NEW RETAINING
 WALLS AND BRIDGE STRUCTURE, INCLUDING TRANSPORTATION OF MATERIAL TO SITE.

 17. CAST-IN-PLACE CONCRETE SHALL CONFORM TO THE FOLLOWING NYSDOT STANDARD
 - SPECIFICATION ITEM NO'S.:

 CONCRETE FOR BRIDGE AND CONCRETE CRIB
 RETAINING WALL FOOTINGS NYSDOT ITEM
 NO. 555.0104 CLASS A, F'c = 4000 PSI.
 - CONCRETE FOR CAST-IN-PLACE CONCRETE WING WALL - NYSDOT ITEM NO. 555.Ø1Ø2 CLASS A, F'c = 4ØØØ PSI.
- 18. CONCRETE REINFORCING BARS FOR CAST—IN—PLACE CONCRETE SHALL CONFORM TO NYSDOT STANDARD SPECIFICATION ITEM NO. 556.Ø2Ø1. SUBMIT FIVE (5) COPIES OF REINFORCING BAR SHOP DRAWINGS TO ENGINEER FOR REVIEW PRIOR TO FABRICATION.
- 19. NON-SHRINK GROUT PAD MATERIAL (FOR BRIDGE RAIL) SHALL BE FIVE STAR FOUNDATION SYSTEM 1 SINGLE LIFT CEMENTITIOUS GROUT AS MANUFACTURED BY FIVE STAR PRODUCTS, INC. OR APPROVED EQUIVALENT. INSTALL GROUT IN STRICT ACCORDANCE WITH MANUFACTURERS REQUIREMENTS.
- 2Ø. CONTRACTOR SHALL COORDINATE WITH ADJACENT PROPERTY OWNERS AND OBTAIN PERMISSION FOR STAGING AREA LOCATION. FULL ACCESS TO ADJACENT PROPERTIES SHALL BE MAINTAINED AT ALL TIMES.

MAINTENANCE AND PROTECTION OF TRAFFIC NOTES

- 1. MAINTENANCE AND PROTECTION OF TRAFFIC DURING CONSTRUCTION OF THE PROJECT SHALL BE PROVIDED BY THE CONTRACTOR.
- 2. ALL TRAFFIC CONTROL SIGNS SHALL BE APPROVED BY THE ESSEX COUNTY DEPARTMENT OF PUBLIC WORKS PRIOR TO USE. ALL SIGNS SHALL CONFORM TO THE NYS MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES LATEST EDITION. ADDITIONAL OR ALTERNATE SIGNS MAY BE REQUIRED BY THE ENGINEER. NO ADDITIONAL PAYMENT SHALL BE MADE FOR SUCH ADDITIONAL OR ALTERNATE SIGNS.
- 3. TEMPORARY CONCRETE BARRIERS AND ALL TRAFFIC CONTROL SIGNS SHALL BE IN PLACE BEFORE COMMENCING DEMOLITION OR CONSTRUCTION WORK
- 4. THE CONTRACTOR SHALL PREPARE A TRAFFIC CONTROL PLAN INDICATING PROPOSED LAYOUT OF ALL TRAFFIC CONTROL SIGNS AND DEVICES FOR REVIEW BY ESSEX COUNTY PRIOR TO COMMENCING THE WORK.
- 5. PROVIDE TEMPORARY FENCING FOR ALL CONSTRUCTION EXCAVATION TO PREVENT PEDESTRIAN ACCESS TO SITE. SUBMIT TEMPORARY FENCING PLAN TO ESSEX CO. FOR REVIEW. MAINTAIN AN APPROVED PEDESTRIAN ACCESS TO ALL STRUCTURES ON EAST SIDE OF STREAM AT ALL TIMES. THE EXISTING FOOTBRIDGE MAY BE RELOCATED AND UTILIZED FOR PEDESTRIAN ACCESS AS APPROVED BY ESSEX COUNTY.

DEMOLITION AND REMOVAL NOTES


- 1. DRAWINGS OF THE EXISTING BRIDGE STRUCTURE ARE NOT AVAILABLE. INFORMATION REGARDING THE EXISTING BRIDGE INDICATED ON THE CONTRACT DRAWINGS IS SCHEMATIC ONLY. THE CONTRACTOR SHALL VISIT THE SITE AND SHALL VERIFY ALL EXISTING DEMOLITION QUANTITIES AND MATERIALS AND SHALL INCLUDE IN HIS BID ALL COSTS ASSOCIATED WITH REQUIRED DEMOLITION OF THE EXISTING BRIDGE AND APPURTENANCES.
- 2. UNLESS SPECIFICALLY NOTED OTHERWISE, ITEMS NOTED IN THE CONTRACT TO BE REMOVED SHALL BE DISPOSED OF OFF SITE. THE COST OF SUPPLYING A DISPOSAL AREA AND TRANSPORTATION TO THAT AREA SHALL BE INCLUDED IN THE BID.
- 3. DEMOLITION AND REMOVAL ITEMS TO BE SALVAGED AND DELIVERED TO ESSEX COUNTY INCLUDE THE FOLLOWING:
 - -ALL EXISTING SIGNAGE
 -EXISTING FLAG POLE
 -ALL EXISTING GUARD RAIL
 -EXISTING FOOT BRIDGE
- 4. DURING DEMOLITION AND REMOVAL OPERATIONS, THE CONTRACTOR SHALL NOT BE PERMITTED TO DROP WASTE CONCRETE, TIMBER, STEEL, DEBRIS OR OTHER MATERIALS INTO THE AREA BELOW THE BRIDGE. PLATFORMS, NETS, SCREENS OR OTHER PROTECTIVE DEVICES SHALL BE USED TO CATCH SUCH MATERIAL. IF, IN THE OPINION OF THE ENGINEER, ADEQUATE PROTECTION DEVICES ARE NOT BEING EMPLOYED, THE WORK SHALL BE SUSPENDED UNTIL ADEQUATE PROTECTION IS PROVIDED. THE COST OF FURNISHING, INSTALLING, MAINTAINING, REMOVING AND DISPOSING OF ALL PLATFORMS, NETS, SCREENS OR OTHER PROTECTIVE DEVICES SHALL BE INCLUDED IN THE BID.

UNAUTHORIZED ALTERATION OR ADDITION TO THIS DOCUMENT IS A VIOLATION OF SECTION 7209 SUBDIVISION 2 OF THE NEW YORK STATE EDUCATION LAW.

REVISIONS

REV. DATE DESCRIPTION

Ø 2/24/97 ISSUED FOR CLIENT REVIEW ISSUED FOR BID & CONSTRUCTION



SCHODER RIVERS ASSOCIATES

CIVIL & STRUCTURAL CONSULTING ENGINEERS Prospect's Rise Professional Offices 2315—2 Route 9N Lake George, New York 12845 (518) 668—2918

| SCALE: | 1"=2Ø' | DRAWN BY: | JVL |
|--------|----------------------|-----------|-----|
| DATE: | 2/14/97 | ENG. BY: | CBS |
| PROJ. | NO: <i>95–3ø3–12</i> | CHK'D BY: | SMR |

CLIENT NAME

ESSEX COUNTY DEPARTMENT
OF PUBLIC WORKS
ELIZABETHTOWN, N.Y.

DRAWING TITLE

ORMSBY BRIDGE REPLACEMENT BIN. 3-3Ø232-Ø

EXISTING BRIDGE & DEMOLITION PLAN

DRAWING NO. SHT. 1 OF 4

REV. 1

EXISTING BRIDGE AND REMOVAL SITE PLAN

1"=2Ø

SEE DRAWING S-2 FOR

LOCATION OF IMPROVEMENT


& CONSTRUCTION BASELINE


----E/P---- EXISTING EDGE OF PAVEMENT


EXISTING WATER VALVE

---196--- EXISTING CONTOUR

—— 196—— NEW CONTOUR







Bridge Ratings

Carried: ORMSBY ROAD Crossed: GULF BROOK CheckValue: 1,758,144,968

Inspection Agency: 13 - Consultant Type of Inspection: 1 - BIENNIAL

GTMS: 107 -- Concrete - Frame

POSTINGS: See Gen Rec Page 1 for Postings at time of inspection.

Further Investigation Needed: No

State Highway Number: 000000 Milepoint: 0 AADT/Yr: 20 /

Orientation: 3 - East Political Unit: 0434 - Town of KEENE Year Built: 1997

Total Spans: 1 Ramp Bridge Attached To Span: NA BIN: NA General Recommendation: 6 Computed Condition Rating: 6.034

| Abutment Ratings: | Beg Abut | End Abut | |
|-----------------------|----------|----------|--|
| Joint with Deck | 8 | 8 | |
| Bearings, Bolts, Pads | 8 | 8 | |
| Seats and Pedestals | 8 | 8 | |
| Backwall | 8 | 8 | |
| Stem (Breastwall) | 7 | 7 | |
| Erosion or Scour | 7 | 7 | |
| Footings | 9 | 9 | |
| Piles | 8 | 8 | |
| Recommendation | 7 | 7 | |

| Wingwall Ratings: | Beg Abut | End Abut | |
|-------------------|----------|----------|--|
| Walls | 7 | 7 | |
| Footings | 9 | 9 | |
| Erosion or Scour | 6 | 6 | |
| Piles | 8 | 8 | |

| Channel Ratings: | Channel |
|------------------|---------|
| Stream Alignment | 7 |

Erosion and Scour 7
Waterway Opening 7
Bank Protection 7

Approach Ratings: Approaches

Drainage 5
Embankment 7
Settlement 5
Erosion 7
Pavement 5
Guide Railing 3

Number of Flags Issued:

RED: 0 Yellow: 0 Safety: 0

Vulnerability Reviews Recommended: 1=Yes, 2=No, 3=NA, X=NotActive

Hydraulic: 2 Overload: X Steel: 3
Collision: 3 Concrete: X Seismic: X

Inspector's Signature: CheckValue: 1,758,144,968 Date: 7/2/2010

Signed copy of this inspection report is available

John Saia, Jr., PE () (Inspector ID:1120059) in the appropriate NYSDOT Regional Office

Reviewed By: Date: 8/24/2010

Signed copy of this inspection report is available in the appropriate NYSDOT Regional Office

Paul Poirier, PE () (QC ID:1120061)

Inspection Date: 7/2/2010 RC: 12 BIN: 3302320 **Span Ratings** Crossed: GULF BROOK CheckValue: 1,758,144,968 Carried: ORMSBY ROAD Deck Element Ratings: 001 Wearing Surface 5 8 Curbs 7 Sidewalks, Fascias Railings, Parapets 5 8 Scuppers Gratings 8 Median 8 Mono Deck Surface 8 Superstructure Ratings: 001 Structural Deck 8 Primary Members 5 Secondary Members 8 8 Paint Joints 8 5 Recommendation

| Pier Ratings: | 001 |
|-----------------------|-----|
| Bearings, Bolts, Pads | 8 |
| Pedestals | 8 |
| Top of Cap or Beam | 8 |
| Stem Solid Pier | 8 |
| Cap Beam | 8 |
| Pier Columns | 8 |
| Footings | 8 |
| Erosion or Scour | 8 |
| Piles | 8 |
| Recommendation | 8 |

| Utility Ratings: | 001 | |
|-----------------------|-----|--|
| Lighting | 8 | |
| Sign Structure | 8 | |
| Utilities and Support | 4 | |

Field Notes

| Fleid Notes: | | | | | |
|--------------|-------------|------------|----------|----------|--------------------|
| Field Date | Arrival | Departure | Temp (C) | Temp (F) | Weather Conditions |
| 7/2/2010 | 11:30:00 AM | 1:30:00 PM | _ | 78 | Sunny |
| , , | | | | _ | 1 |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

Inspection Notes

Carried: ORMSBY ROAD Crossed: GULF BROOK CheckValue: 1,758,144,968

Note ID: 1U1033023200000

Approaches: Guide Railing -- Rated 3, Was 3

Referenced Photos: "1", "2"

2010

The begin left, w-section guide rail has been impacted. The end timber posts are leaning and the rail is disconnected from the second post from the bridge. The end post is broken and not attached to the end of rail. The rail is slightly loose; rates 3. This is a low speed, low volume road with good site distance along the approach. No safety flag is warranted at this time.

The guide rail in the remaining quadrants is in fair to good condition and rates 5.

Note ID: 1U1033023200001

Span 001 -- Superstructure: Primary Members -- Rated 5, Was 7

Referenced Photos: "3", "4", "5"

2010

The bridge is comprised of four precast concrete frame units. Within the joints between the units, there is a build up of efflorescence and rust staining with areas of active leaking and stalactites. See Photo 3. At the fascia edges of unit 1 and unit 4, there is fine mapcracking with damp concrete. See photo 4. Unit 4 appears to have transverse cracking that is fine and tight. See photo 5.

Overall, there were no areas of hollow sounding concrete found. The rating for unit 4 is lowered to 5; the remaining units rate 6.

Note ID: 1U1033023200002

Span 001 -- Utilities: Utilities and Support -- Rated 4, Was 7

Referenced Photos: "6"

2010

A small diameter pvc pipe extends across the bridge, adjacent to the water main pipe. At midspan, the pipe is disconnected at the coupling. The exposed wire is intact with no defects to the wire casing. See photo 6. At end left, the conduit comes out of the ground to meet the conduit spanning the bridge, but there is no 90 degree elbow. The wire/cable is exposed with no defects to the wire casing. The rating is lowered to 4. No safety flag is warranted at this time.

Inspection Photos in Photo Number Order

Carried: ORMSBY ROAD Crossed: GULF BROOK CheckValue: 1,758,144,968

Begin Left Guide Rail



Begin Left Guide Rail -Post 2




Inspection Photos in Photo Number Order

Carried: ORMSBY ROAD Crossed: GULF BROOK CheckValue: 1,758,144,968

Underside of Bridge, Left Side from End



Precast Unit 1, Left Side near Mid-Span



Inspection Photos in Photo Number Order

Carried: ORMSBY ROAD Crossed: GULF BROOK CheckValue: 1,758,144,968

Precast Unit 4, Right Side near Mid-Span



Conduit Near Mid-Span, Left Side



Inspection Sketches in Sketch SysID Order


Carried: ORMSBY ROAD Crossed: GULF BROOK CheckValue: 1,758,144,968

Sketch ID: 1U1033023200001 Sketch Filename: 10photo-location.wpd

General Sketch for Bridge

Referenced Photos:

Photo Location Plan



Inspection Sketches in Sketch SysID Order


Carried: ORMSBY ROAD Crossed: GULF BROOK CheckValue: 1,758,144,968

Sketch ID: 1U1033023200002 Sketch Filename: 10Bd227.wpd

Stream Channel: Erosion and Scour -- Rated 7, Was 7

Referenced Photos:

Channel Cross-Section Along Fascias



Inspection Sketches in Sketch SysID Order

BIN: 3302320

Carried: ORMSBY ROAD Crossed: GULF BROOK CheckValue: 1,758,144,968

Sketch ID: 1U1033023200003 Sketch Filename: 10BD226.wpd

Stream Channel: Erosion and Scour -- Rated 7, Was 7

Referenced Photos:

Channel Cross-Section Readings

Insp. Date: 07/02/2010

| BD 226 | | | | |
|--------|-------------|--------|----------|--|
| NYSDOT | BRIDGE INSF | PECTIO | N REPORT | CHANNEL CROSS-SECTION READINGS (Feet) |
| SHEET | 2 | OF | 2 | READINGS (Feet) |
| | | | | |

| STA. | LE | FT SIE | DE REA | DING | S: | STA. | RIG | SHT SI | DE RE | ADING | S: |
|--------|-------------|-------------|--------------|--------------|--------------|--------|-------------|-------------|--------------|--------------|--------------|
| YEAR > | 2004 (m) | 2006 (m) | 2006 (ft) | 2008 (ft) | 2010 (ft) | YEAR > | 2004 (m) | 2006 (m) | 2006 (ft) | 2008 (ft) | 2010 (ft) |
| 1 | 4.0 | 4.0 | 13.1 | 13.1 | 13.1 | 1 | 3.8 | 3.9 | 12.8 | 12.1 | 12.4 |
| 2 | 4.1 | 4.2 | 13.8 | 13.5 | 13.6 | 2 | 4.0 | 4.0 | 13.1 | 12.8 | 12.7 |
| 3 | 4.2 | 4.1 | 13.5 | 13.1 | 13.3 | 3 | 3.9 | 4.0 | 13.1 | 12.8 | 12.8 |
| 4 | 4.1 | 4.1 | 13.5 | 13.1 | 13.2 | 4 | 3.9 | 3.8 | 12.5 | 12.5 | 12.5 |
| 5 | 3.7 | 3.6 | 11.8 | 12.1 | 12.1 | 5 | 3.5 | 3.5 | 11.5 | 11.5 | 11.4 |
| | | | | | | | | | | | |
| WL @ 3 | 3.8 | 3.8 | 12.5 | 12.5 | 12.6 | WL @ 3 | 3.7 | 3.7 | 12.1 | 12.1 | 12.2 |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | \vdash |
| | | | | | | | | | | | |
| | | | | | | | | | | | |

Gen. Rec., Postings, Federal Ratings, etc.

Carried: ORMSBY ROAD Crossed: GULF BROOK CheckValue: 1.758.144.968

Overall Condition:

GENERAL RECOMMENDATION: 6

Computed Condition Rating: 6.034

Problems Requiring Action:

NO Further Investigation Needed

NO Flags Issued

POSTINGS:

Inspector Confirmed existing Posting data as correct.

Posted Vertical Clearance ON the bridge is: No Posting

Posted Vertical Clearance UNDER the bridge is: No Posting

No Load Restriction is posted on this bridge

Overloads Observed:

NO Overload Vehicles were observed on this bridge

FEDERAL RATINGS:

NBI Deck Condition: 8

NBI Superstruct Condition: 7

NBI Substruct Condition: 9

NBI Channel Condition: 8

NBI Culvert Condition: N

Diving Inspection Needs:

Diving Inspection Required? No Date of Last Diving Inspection: No Date

Inventory Problems:

Inventory Problems Exist? No

Miscellaneous:

Time Required to Inspect Bridge: 2 Hours

Lane Closure Needs: None Required

No Railroad Flagging Required

No Pedestrian Fence

No Snow Fence

The BIN Plate is in OK condition

| Ins | pection Date: 7/2/2 | 010 | RC: 12 | BIN: 330232 | 20 |
|-----|----------------------|---------------------|---------------------------|-------------|----|
| | Gen. Re | c., Postings, Fede | ral Ratings, etc. | | |
| | Carried: ORMSBY ROAD | Crossed: GULF BROOK | CheckValue: 1,758,144,968 | | |
| | | | | | |

Special Emphasis Inspection Required:

Non-Redundant/Fracture Critical Members - No Pin and Hangers - No Fatigue-Prone Welds - No Non-Categorized Fatigue-Prone Details - No Other (Specified in Text) - No

Special Emphasis Details:

No Special Emphasis Inspection Required.

General Notes To the Next Inspector:

2010 Access: walking, step ladder

The Bin plate is in good condition, located on the begin right wingwall.

Improvements Observed:

| 2010: None. | | | |
|-------------|--|--|--|
| | | | |
| | | | |

Review Progress and Personnel Present at Inspection

Carried: ORMSBY ROAD Crossed: GULF BROOK CheckValue: 1,758,144,968

Inspection Submission Status:

Submitted to QC Engineer on: 8/24/2010 QC Submission Number: U0100701

QC Review Completed: 8/24/2010 QC Engineer: Paul Poirier

Submitted to Liaison Engineer on: 8/24/2010 Liaison Submission Number: 01018

Liaison Review Completed: 9/17/2010

Liaison Engineer: TODD M. HERMANN

Submitted for BIIS Processing on: 9/17/2010

BIIS Submission Number: .kp1

Current Status: Keypunched, Sent to BIIS

Check Value: 1,758,144,968

Personnel Present During Inspection:

John Saia, Jr. - Team Leader

Derek McDonagh - Assistant Team Leader

Inspection Access Requirements

Carried: ORMSBY ROAD Crossed: GULF BROOK CheckValue: 1,758,144,968

Equipment Required for Inspection

No Access Requirement Changes Noted During This Inspection.

This Listing is from the Inventory Database.

ACCESS CATEGORIES FOR ENTIRE BRIDGE

Required: Walking, Step Ladder

ACCESS CATEGORIES FOR SPAN 1 Required: Walking, Step Ladder

Culvert Measurements

Carried: ORMSBY ROAD Crossed: GULF BROOK CheckValue: 1,758,144,968


Culvert Measurements

NO CULVERT DATA FOR BIN 3302320

RC: 12 BIN: 3302320

Carried: ORMSBY ROAD Crossed: GULF BROOK


3302320_LOCATION_MAP.JPG



RC: 12 BIN: 3302320

Carried: ORMSBY ROAD Crossed: GULF BROOK

3302320_QUAD_MAP.JPG



RC: 12 BIN: 3302320

Carried: ORMSBY ROAD

Crossed: GULF BROOK


AbutmentBegin.jpg



RC: 12 BIN: 3302320

Carried: ORMSBY ROAD Crossed: GULF BROOK

AbutmentEnd.jpg



RC: 12 BIN: 3302320

Carried: ORMSBY ROAD Crossed: GULF BROOK

ApproachBegin.jpg



RC: 12 BIN: 3302320

Carried: ORMSBY ROAD Crossed: GULF BROOK

ApproachEnd.jpg



RC: 12 BIN: 3302320

Carried: ORMSBY ROAD Crossed: GULF BROOK

ElevationRight.jpg



RC: 12 BIN: 3302320

Carried: ORMSBY ROAD Crossed: GULF BROOK

FeatureCrossedLeft.jpg



RC: 12 BIN: 3302320

Carried: ORMSBY ROAD Crossed: GULF BROOK

FeatureCrossedRight.jpg



RC: 12 BIN: 3302320

Carried: ORMSBY ROAD Crossed: GULF BROOK

Framing.jpg



RC: 12 BIN: 3302320

Carried: ORMSBY ROAD Crossed: GULF BROOK

Utility.jpg

