

# ADDENDUM NO. 3

## 2021 21-400 Tracy Road Over Ash Craft Brook Culvert Replacement

Essex County, NY

February 23, 2021

### TO ALL HOLDERS OF BIDDING DOCUMENTS:

This Addendum, issued to bid document holders of record, indicates clarifications to the bid documents for the 2021 21-400 Tracy Road over Ash Craft Brook Culvert Replacement project. All information and clarifications described herein shall be incorporated into the Contractor's bid proposal. This Addendum is part of the Contract Documents. Adjustments required by each item shall be understood to apply to all document references affected by the clarifications described.

1. Question Received: One item that requires clarification of would be the concrete pay items -

Item 555.0105	Footing Concrete Class A	31 CY
Item 555.08	Footing Concrete Class HP	31 CY
Item 555.09	Concrete for Structures Class HP	18 CY

Please clarify what areas of cast in place concrete the pay items will be utilized.

*Response: Items 555.0105 and 555.08 are for the cast in place concrete footings for the three-sided culvert structure and the precast wingwall units. Either item may be utilized depending on whether the concrete is placed by pumping. For the purposes of bidding, half of the total quantity was allocated to each of the two items. The contractor will be paid for the item that is delivered in accordance with the corresponding unit price in his/her bid. Item 555.09 is for the cast in place headwall.*

**END OF ADDENDUM NO. 3**