



ESSEX COUNTY OFFICE OF COMMUNITY RESOURCES

7514 Court Street · P.O. Box 217 · Elizabethtown, New York 12932
Telephone (518) 873-3426 · Fax (518) 873-3751

Anna Reynolds
Director

Rob Wick
Project Manager

TO: All Bidders / Respondents

FROM: Essex County Community Resources, on behalf of the Town of Willsboro

DATE: February 3rd, 2020

SUBJECT: Addendum #2 Willsboro Veterans Monument Reconstruction (RE BID)

1. Correction to Bid Form and template Pay App, where concrete and rebar figures were duplicative. Remove outdated forms and include the attached.

END OF ADDENDUM # 2

VETERANS MONUMENT RECONSTRUCTION - BASE BID

ITEM No.	ITEM	ESTIMATED QTY	UNIT	COMMENTS	BID PRICE PER UNIT	BID PRICE TOTAL
1	GENERAL, MOB & DE-MOB*	1	LS	*INCLUDE OVH & PROFIT		
2	MAINTAIN EROSION & SEDIEMENT CONTROL	1	LS			
3	GRANITE CURBING	69	LF			
4	POROUS CONCRETE (6" THICK)**	297	CF	**6" THICK APPLICATION		
5	TYPICAL CONCRETE	159.62	CF			
	MEMORIAL FOOTING CONCRETE	53.67	CF			
	FLAG POLE CONCRETE	104.5	CF			
	ELECTRICAL PANEL CONCRETE	1.45	CF			
6	REBAR	721.695	LBS			
	FLAG POLE REBAR	537.084	LBS			
	MEMORIAL FOOTING REBAR	184.611	LBS			
7	SELECT GRANULAR FILL	34.5	CF			
8	TOPSOIL	135	CF			
9	B-12 STONE	593	CF			
10	LANDSCAPE EDGING	45	LF			
11	LANDSCAPE MULCH	52	CF			
12	LANDSCAPE SEEDING	4	LBS			
13	FILTER FABRIC	1393	SF			
14	MEMORIAL - COLUMN	2	EA			
15	MEMORIAL - ARCH	1	EA			
16	MEMORIAL - BRONZE SEAL	5	EA			
17	MEMORIAL - #7 PINS	10	LF			
18	FLAG POLE LIGHTING	2	EA			
19	ELECTRICAL CONDUIT 1"	20	LF			
20	ELECTRICAL GFCI RECEPTACLE	1	EA			
21	ELECTRICAL PANEL	1	EA			
22	FLAG POLE - POLE SETTING***	1	LS	***INCLUDES SPUN COLLAR, STEEL CENTERING WEDGES, STEEL SLEEVE, WATERPROOF COMPOUND, HARDWOOD WEDGES, DRY SAND, LIGHTNING GROUND SPIKE, TWO STEEL SUPPORT PLATES, AND ASSOCIATED WELDING.		
23	FLAG POLE - BASE BRONZE PLATE	2	EA			
24	BENCH FEET	16	EA			
25	BENCH SLABS	8	EA			
26	BENCH PINS	32	EA			
27	GRANITE PAVER AREA	593	SF	2" THICK PAVERS OVER AREA		
28	SAND SETTING BED	106	CF			

Progress Estimate - Unit Price Work

Contractor's Application

For (Contract):		General Construction (GC)			Project Number:		P-0064-2017			Application Number:			
Application Period:		Start			Finish:				Application Date:				
A					B	C	D	E	F				
Item					Bid Item Quantity	Unit Price	Bid Item Value (\$)	Estimated Quantity Installed	Value of Work Installed to Date	Materials Presently Stored (not in C)	Total Completed and Stored to Date (D + E)	% (F / B)	Balance to Finish (B - F)
Bid Item No.	Description	Units											
1	GENERAL, MOB & DE-MOB*	LS	1								\$ -		\$ -
2	MAINTAIN EROSION & SEDIEMENT CONTROL	LS	1								\$ -		\$ -
3	GRANITE CURBING	LF	69								\$ -		\$ -
4	POROUS CONCRETE (6" THICK)	CF	297								\$ -		\$ -
5	TYPICAL CONCRETE	CF	159.62								\$ -		\$ -
	MEMORIAL FOOTING CONCRETE	CF	53.67								\$ -		\$ -
	FLAG POLE CONCRETE	CF	104.5								\$ -		\$ -
	ELECTRICAL PANEL CONCRETE	CF	1.45								\$ -		\$ -
6	REBAR	LBS	721.695								\$ -		\$ -
	FLAG POLE REBAR	LBS	537.084								\$ -		\$ -
	MEMORIAL FOOTING REBAR	LBS	184.611								\$ -		\$ -
7	SELECT GRANULAR FILL	CF	34.5								\$ -		\$ -
8	TOPSOIL	CF	135								\$ -		\$ -
9	B-12 STONE	CF	593								\$ -		\$ -
10	LANDSCAPE EDGING	LF	45								\$ -		\$ -
11	LANDSCAPE MULCH	CF	52								\$ -		\$ -
12	LANDSCAPE SEEDING	LBS	4								\$ -		\$ -
13	FILTER FABRIC	SF	1393								\$ -		\$ -
14	MEMORIAL - COLUMN	EA	2								\$ -		\$ -
15	MEMORIAL - ARCH	EA	1								\$ -		\$ -
16	MEMORIAL - BRONZE SEAL	EA	5								\$ -		\$ -
17	MEMORIAL - #7 PINS	LF	10								\$ -		\$ -
18	FLAG POLE LIGHTING	EA	2								\$ -		\$ -
19	ELECTRICAL CONDUIT 1"	LF	20								\$ -		\$ -
20	ELECTRICAL GFCI RECEPTACLE	EA	1								\$ -		\$ -
21	ELECTRICAL PANEL	EA	1								\$ -		\$ -
22	FLAG POLE - POLE SETTING	LS	1								\$ -		\$ -
23	FLAG POLE - BASE BRONZE PLATE	EA	2								\$ -		\$ -
24	BENCH FEET	EA	16								\$ -		\$ -
25	BENCH SLABS	EA	8								\$ -		\$ -
26	BENCH PINS	EA	32								\$ -		\$ -
27	GRANITE PAVER AREA	SF	593								\$ -		\$ -
28	SAND SETTING BED	CF	106								\$ -		\$ -
27-A	UNILOCK PAVERS	SF	593								\$ -		\$ -
28-A	UNILOCK SETTING BED	CF	106								\$ -		\$ -
Totals							\$ -		\$ -	\$ -	\$ -		\$ -