

ADDENDUM NO. 2

2018 - Bell Tower Repair Project

Essex County, NY

June 1, 2018

TO ALL HOLDERS OF BIDDING DOCUMENTS:

This Addendum, issued to bid document holders of record, indicates clarifications to the bid documents for the *2018 - Bell Tower Repair Project* project. All clarifications described herein shall be incorporated into the Contractor's bid proposal. This Addendum is part of the Contract Documents. Adjustments required by each item shall be understood to apply to all document references affected by the clarifications described.

1. **DRAWINGS:** It is acceptable to substitute the following built-up engineered lumber wood beams for the heavy timber wood beams shown on the Drawings as follows:
 - a. 8 x 10 Heavy Timber Beam at (2) locations: (4) plys of 1 3/4" x 9 1/2" L.V.L Beam.
 - b. 10 x 10 Heavy Timber Beam at (2) locations: (5) plys of 1 3/4" x 9 1/2" L.V.L. Beam.L.V.L indicates Laminated Veneer Lumber and shall be "MICROLAM" by Weyerhaeuser, or equivalent with minimum design values of "E" = 2000 ksi. and "Fb" = 2.9 ksi. Each ply shall be nailed together with (3) 16d nails at 16" center to center. (Note that L.V.L material shall not be substituted for the heavy timber material required at splices of damaged existing heavy timber. This material must match the existing as noted on the Drawings.)

END OF ADDENDUM NO. 2