

ADDENDUM NO. 2

to the Contract Documents
for the Construction of the

Jay Community Center Emergency Shelter Upgrades

at
11 SCHOOL LANE
AU SABLE FORKS, NY 12912

TO ALL HOLDERS OF CONTRACT DOCUMENTS:

Your attention is directed to the following interpretations of changes in and additions to the Contract Documents for the construction of the **JAY COMMUNITY CENTER EMERGENCY SHELTER UPGRADES** project at the Jay Town Hall Au Sable Forks, New York. This Addendum is part of the Contract Documents in accordance with the provisions of General Conditions, Article 1.1.

GENERAL:

1. Refer to this document for summary of responses to inquiries received.
2. There is no change to the bid opening date and time.

ON THE PROJECT DRAWINGS:

1. On Sheet AD-101: **ADD** "Remove existing acoustical ceiling tile ceiling and associated T's and hangers" to both Men's and Women's Bathrooms.

RFI CLARIFICATIONS:

Q: Are we to assume there is an existing ceiling that needs to be demoed in each of these rooms? Please advise what the existing material is that needs to be removed or that is remaining.

A: Existing acoustical tile ceilings and associated T's and attachments must be demolished in both bathrooms. Ceilings in kitchen to remain. Patch and paint kitchen gypsum ceiling after installation of new lighting.

Q: The lead tile items in the report are not scheduled to be removed is that correct? Precautions will just have to be taken when attaching material to them? Please confirm.

A: Lead tile will not be removed. Precautions should be used when attaching the FRP wainscoting over the existing wall tiles.

Q: The abatement items will be removed as they are part of the scope.

A: Kitchen flooring to be removed for installation of finish floor as scheduled.

Jay Community Center Emergency Shelter Upgrades
655.006.001
June 26, 2019

Q: *Is this a tax exempt project?*

A: *Yes, this is a tax exempt project.*

Q: *On A101, what are C, H and I representing?*

A: *C denotes carbon monoxide detector. H denotes heat detector. J denotes monitor hood suppression system. See E-102.z.*

END OF ADDENDUM

C&S ENGINEERS, INC.



D.H. Chung, AIA LEED AP
Senior Project Architect