



ESSEX COUNTY OFFICE OF THE MANAGER

7551 Court Street · P.O. Box 217 · Elizabethtown, New York 12932
Telephone (518) 873-3332 · Fax (518) 873-3339

Daniel L. Palmer
County Manager

Linda M. Wolf
Purchasing Agent

TO: All Bidders

FROM: Linda Wolf, CPA, Purchasing Agent

DATE: July 9, 2020

SUBJECT: Addendum #2 CONCRETE BOX CULVERT MATERIALS

This Addendum, issued to bid document holders of record, indicates changes to the bid documents for the *Concrete Box Culvert Materials Bid Opening July 16, 2020.*

Bid Clarifications:

Wing Walls: Sheet BD-CB1E-R1 does not have wing wall data or geotechnical data since wing walls are not required. No precast cut off wall is required as well. Plan calls only for the box culvert and the installation details of BD-CB1E-R1 pertaining to the precast box, with information identified on the plan sheet for dimensions and length.

Sediment Bags: The use of a sediment bag for Dewatering, so long as it is performed following NYSDEC Erosion and sediment control standards can be utilized but will likely need to be utilized in conjunction with other erosion and sediment control measures.

Stream Bed: The use of native stream bed material is required.

END OF ADDENDUM # 2