



ESSEX COUNTY OFFICE OF COMMUNITY RESOURCES

7551 Court Street · P.O. Box 217 · Elizabethtown, New York 12932
Telephone (518) 873-3426 · Fax (518) 873-3751

Anna Reynolds
Director

Rob Wick
Project Manager

TO: All Bidders

FROM: Rob Wick, PMP Project Mgr

DATE: August 18th, 2020

SUBJECT: Addendum #1 Elizabethtown Water Well Drilling RFP

1. Correction to RFP Appendix K:

- a. Clarifications to Appendix K - Deliverables Cost Table (attached)**

END OF ADDENDUM # 1

APPENDIX K: DELIVERABLES TABLE (REVISED)

DELIVERABLES	RATE	BASIS OF COMPENSATION	EST. UNITS
GENERAL REQUIREMENTS TOTAL:			
Project Schedule Updates		LS	1
Funding Agency Reporting		LS	1
Drilling Logs / Reporting		LS	1
TOTAL FOR EACH TEST WELL:			
Mob & De-Mob for drilling platform to/from Site		LS / EA.	1
Discharge / Site Controls & Pollution Prevention		LS / EA.	1
Generator, Pipe & Pump Allowance		LS / EA.	1
Drilling: 6" Test wells:		UP	200 LF
Overburden drilling & installation of temp surface casing (25' depth for sanitary seal):		LS / EA.	1
Drive Shoe:		LS / EA.	1
Well Screen (inclusive of riser, K-packer and bottom plate with J-hook) 6" temp:		LS / EA.	1
Sieve Analysis:		LS / EA.	1
Cement grout of sanitary seal and removal of temporary surface casing:		LS / EA.	1
Site Restoration		LS / EA.	1
Lockable Well Cap:		LS / EA.	1
Set & Pull Test Pump:		LS / EA.	1
4-HR Step Test:		LS / EA	1
<i>TEST WELL DEVELOPMENT</i>		<i>LS / EA</i>	<i>1</i>
<i>REMOVE SCREEN FOR ADD'L TEST WELL</i>		<i>LS / EA</i>	<i>1</i>

1) All cost proposal units are required to be provided for individual wells for the purposes of the RFP, though it is anticipated that a minimum of three (3) test wells are required for the project.

2) These figures are Not-to-Exceed Hourly Estimates. For State Revolving Fund compliance, these figures must have an approved contract Amendment prior to exceeding these estimates for additional test wells under the professional services agreement.